# UTILITY PATENT APPLICATION TRANSMITTAL (Large Entity)

(Only for new ponprovisional applications under 37 CFR 1.53(b))

Docket No. 89190.145700/DP-302200

Total Pages in this Submission

### TO THE ASSISTANT COMMISSIONER FOR PATENTS

**Box Patent Application** Washington, D.C. 20231

| Transmitted herewith | for filing under 35 U.S.C. | 111(a) and 37 C.F.R. | 1.53(b) is a new utility | patent application for an |
|----------------------|----------------------------|----------------------|--------------------------|---------------------------|
| invention entitled:  |                            |                      |                          |                           |

| HYD             |             | ntitled<br>CARI |           | EED EMIS      | SION S          | CRUBBER W                         | ITH LOW REST                         | RICTION                    | .s. PTO<br>16988 |
|-----------------|-------------|-----------------|-----------|---------------|-----------------|-----------------------------------|--------------------------------------|----------------------------|------------------|
| l<br>nd inv     | ente        | d by:           |           |               |                 |                                   |                                      |                            |                  |
|                 |             |                 |           | harles H. Co  | vert, S         | usan S. LaBine                    |                                      |                            | 160 D            |
| f a CC          | DNT         | INUA            | TION A    | PPLICATION    | <b>)N</b> , che | eck appropriate                   | e box and supply                     | the requisite information: |                  |
| i C             | onti        | nuat            | ion 🗆     | Division      | al 🗆            | Continuation                      | on-in-part (CIP)                     | of prior application No.:  |                  |
| Vhich           | is a        | :               |           |               |                 |                                   |                                      |                            |                  |
| Ō C             | onti        | nuat            | ion 🗆     | Division      | al 🗆            | ] Continuati                      | on-in-part (CIP)                     | of prior application No.:  |                  |
| ∜hich           | is a        | :               |           |               |                 |                                   |                                      |                            |                  |
| ☐ C             | onti        | nuat            | ion [     | ☐ Division    | al 🗆            | ] Continuati                      | on-in-part (CIP)                     | of prior application No.:  |                  |
| ii<br>ii:       |             |                 |           |               |                 |                                   |                                      |                            |                  |
| nclos           | sed a       | are:            |           |               |                 | Annlica                           | tion Elements                        |                            |                  |
| Will Hall       |             |                 |           |               |                 | • •                               |                                      |                            |                  |
| ۵۱.<br>۱۳.      | $\boxtimes$ | Filin           | g fee as  | s calculated  | and tra         | ansmitted as d                    | lescribed below                      |                            |                  |
| <u>[]</u><br>2. | $\boxtimes$ | Spe             | cificatio | n having      |                 | 28                                | pages and i                          | ncluding the following:    |                  |
|                 |             |                 |           | _             |                 |                                   |                                      |                            |                  |
|                 | a.          | $\boxtimes$     | Descri    | ptive Title o | f the In        | vention                           |                                      |                            |                  |
|                 | b.          | $\boxtimes$     | Cross     | References    | to Rei          | ated Application                  | ons (if applicable)                  |                            |                  |
|                 | C.          |                 | Staten    | nent Regard   | ling Fe         | derally-sponso                    | ored Research/De                     | evelopment (if applicable) |                  |
|                 | d.          |                 | Refere    | ence to Mici  | ofiche .        | Appendix <i>(if a<sub>l</sub></i> | oplicable)                           |                            |                  |
|                 | e.          | $\boxtimes$     | Backg     | round of the  | Inven           | tion                              |                                      |                            |                  |
|                 | f.          | X               | Brief S   | Summary of    | the Inv         | rention                           |                                      |                            |                  |
|                 | g.          |                 |           |               |                 | rawings <i>(if dra</i>            | awinas filed)                        |                            |                  |
|                 |             | _<br>⊠          |           | ed Descripti  |                 |                                   | ·· <b>·g</b> - ···· <del>· •</del> / |                            |                  |
|                 |             |                 |           | •             |                 | olow                              |                                      |                            |                  |
|                 |             | X               |           | (s) as Class  |                 |                                   |                                      |                            |                  |
|                 | j.          | $\boxtimes$     | Abstra    | act of the Di | sclosur         | е                                 |                                      |                            |                  |

# UTILITY PATENT APPLICATION TRANSMITTAL (Large Entity)

(Only for new nonprovisional applications under 37 CFR 1.53(b))

Docket No. 89190.145700/DP-302200

Total Pages in this Submission

#### **Application Elements (Continued)** Drawing(s) (when necessary as prescribed by 35 USC 113) Formal Number of Sheets a. 🔲 b. 🛛 Informal Number of Sheets ☑ Oath or Declaration a. 🛛 Newly executed (original or copy) ☐ Unexecuted b. Copy from a prior application (37 CFR 1.63(d)) (for continuation/divisional application only) c. With Power of Attorney ☐ Without Power of Attorney DELETION OF INVENTOR(S) Signed statement attached deleting inventor(s) named in the prior application, see 37 C.F.R. 1.63(d)(2) and 1.33(b). ☐ Incorporation By Reference (usable if Box 4b is checked) The entire disclosure of the prior application, from which a copy of the oath or declaration is supplied under Į. Di Box 4b, is considered as being part of the disclosure of the accompanying application and is hereby incorporated by reference therein. A P Computer Program in Microfiche (Appendix) Nucleotide and/or Amino Acid Sequence Submission (if applicable, all must be included) **₌.7.** 7 a. Paper Copy **F** ð١ b. Computer Readable Copy (identical to computer copy) E) E3 c. Statement Verifying Identical Paper and Computer Readable Copy **Accompanying Application Parts** Assignment Papers (cover sheet & document(s)) ☐ 37 CFR 3.73(B) Statement (when there is an assignee) 10. ☐ English Translation Document (if applicable) Information Disclosure Statement/PTO-1449 12. □ Preliminary Amendment 13. Acknowledgment postcard 14. Certificate of Mailing First Class Express Mail (Specify Label No.): EL407218079US

# UTILITY PATENT APPLICATION TRANSMITTAL (Large Entity)

(Only for new nonprovisional applications under 37 CFR 1.53(b))

Docket No. 89190.145700/DP-302200

Total Pages in this Submission

|                                      | Accompanying Application Parts (Continued) |  |  |  |  |  |  |  |  |  |
|--------------------------------------|--|--|--|--|--|--|--|--|--|--|
| 15.                                  |  | Certified Copy of Priority Document(s) (if foreign priority is claimed)  |  |  |  |  |  |  |  |  |
| 16.                                  |  | Additional Enclosures (please identify below):   |  |  |  |  |  |  |  |  |
|                                      |  |  |  |  |  |  |  |  |  |  |
|                                      |  | Request That Application Not Be Published Pursuant To 35 U.S.C. 122(b)(2)  |  |  |  |  |  |  |  |  |
| The sum are one are some and sum one |  | Pursuant to 35 U.S.C. 122(b)(2), Applicant hereby requests that this patent application not be published pursuant to 35 U.S.C. 122(b)(1). Applicant hereby certifies that the invention disclosed in this application has not and will not be the subject of an application filed in another country, or under a multilateral international agreement, that requires publication of applications 18 months after filing of the application.  |  |  |  |  |  |  |  |  |
|                                      |  | Warning  |  |  |  |  |  |  |  |  |
| tr                                   |  | An applicant who makes a request not to publish, but who subsequently files in a foreign country or under a multilateral international agreement specified in 35 U.S.C. 122(b)(2)(B)(i), must notify the Director of such filing not later than 45 days after the date of the filing of such foreign or international application. A failure of the applicant to provide such notice within the prescribed period shall result in the application being regarded as abandoned, unless it is shown to the satisfaction of the Director that the delay in submitting the notice was unintentional. |  |  |  |  |  |  |  |  |
|                                      |  |  |  |  |  |  |  |  |  |  |

# UTILITY PATENT APPLICATION TRANSMITTAL (Large Entity)

(Only for new nonprovisional applications under 37 CFR 1.53(b))

Docket No. 89190.145700/DP-302200

Total Pages in this Submission

#### **Fee Calculation and Transmittal**

| CLAIMS AS FILED   |   |          |        |           |                        |  |          |  |  |  |
|---|---|----------|--------|-----------|------------------------|--|----------|--|--|--|
| For   | #Filed  | #Allowed | #Extra |           | Rate                   |  | Fee      |  |  |  |
| Total Claims  | 47  | - 20 =   | 27     | х         | \$18.00                |  | \$486.00 |  |  |  |
| Indep. Claims   | dep. Claims 6 - 3 = 3 x \$80.00                     |          |        |           |                        |  | \$240.00 |  |  |  |
|   | ୌଷ୍ଟାtiple Dependent Claims (check if applicable) 🔲 |          |        |           |                        |  |          |  |  |  |
|   | BASIC FEE   |          |        |           |                        |  |          |  |  |  |
| 5.4 ×   | OTHER FEE (specify purpose)                         |          |        |           |                        |  |          |  |  |  |
| American<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Company<br>Compa | TOTAL FILING FEE \$1,436                            |          |        |           |                        |  |          |  |  |  |
| <ul> <li>□ A check in the amount of to cover the filing fee is enclosed.</li> <li>☑ The Commissioner is hereby authorized to charge and credit Deposit Account No. 10-0223 as described below. A duplicate copy of this sheet is enclosed.</li> <li>☑ Charge the amount of \$1,436.00 as filing fee.</li> <li>☑ Credit any overpayment.</li> <li>☑ Charge any additional filing fees required under 37 C.F.R. 1.16 and 1.17.</li> <li>□ Charge the issue fee set in 37 C.F.R. 1.18 at the mailing of the Notice of Allowance, pursuant to 37 C.F.R. 1.311(b).</li> </ul>  |   |          |        |           |                        |  |          |  |  |  |
| Dated: October 26   | , 2000  |          |        | eg. No. 3 | Kisicki, Esq.<br>8,205 |  |          |  |  |  |

Page 4 of 4

cc:

39 State Street

Tel: (716) 262-3640

Fax: (716) 262-4133

JAECKLE FLEISCHMANN & MUGEL, LLP

Rochester, New York 14614-1310

#### HYDROCARBON BLEED EMISSION SCRUBBER WITH LOW RESTRICTION

#### CROSS REFERENCE TO RELATED APPLICATIONS

This application claims the benefit of U.S. Provisional Patent Application Serial No. 60/192,917, filed March 29, 2000.

#### **TECHNICAL FIELD**

The present invention relates to evaporative emissions control systems in motor vehicles.

#### **BACKGROUND OF THE INVENTION**

Motor vehicles emit hydrocarbons as a result of the evaporation of fuel. Generally, such evaporative emissions result from the venting of fuel vapors from the fuel tank due to diurnal changes in ambient pressure and/or temperature, the vaporization of fuel by a hot engine and/or exhaust system, and the escape of fuel vapors during refueling of the vehicle. The venting of fuel vapor from the fuel tank due to diurnal pressure and/or temperature changes (i.e., diurnal emissions) is responsible for a majority of evaporative emissions. Diurnal changes in pressure and/or temperature cause air to flow into and out of the fuel tank. Air flowing out of the fuel tank inevitably carries fuel vapor which is created by the evaporation of fuel into the air contained above the fuel within the fuel tank. If this flow of air is left untreated and is allowed to escape directly into the atmosphere, undesirable emissions occur.

One way in which motor vehicle manufacturers have reduced the level of diurnal emissions is through the use of evaporative canisters. A detailed discussion of the structure and operation of an evaporative canister is presented in U.S. Patent No. 5,910,637, the disclosure of which is incorporated herein by reference.

Generally, an evaporative canister has a vapor inlet, a purge port and a vent port. The vapor inlet is fluidly connected by a vapor conduit to the air space in the fuel tank. Diurnal changes in pressure and/or temperature causes air within the fuel tank to flow through the vapor conduit and into the evaporative canister via the vapor inlet. The air carries fuel vapor and/or hydrocarbons. The evaporative canister contains a sorbent material, such as an activated carbon, that strips fuel vapor from the air as it flows through the canister. The treated air then flows out the vent port and into the atmosphere. The purge port is fluidly connected by a valved purge conduit to the combustion air intake of the motor vehicle engine. When the engine is running, the combustion air intake is at sub-atmospheric pressure, and the valve is opened to thereby connect the purge port to the combustion air intake. Fresh air is drawn by the sub-atmospheric pressure through the vent port and into the evaporative canister. The fresh air flows through the sorbent material, out the purge port and into the combustion air intake. The flow of fresh air through the evaporative canister strips the sorbent material of stored fuel vapor and/or hydrocarbons, thereby purging the evaporative canister of hydrocarbons.

However, minute levels of hydrocarbons remain stored in the sorbent material of a purged evaporative canister. Bleed emissions are believed to result from the release of these stored hydrocarbons (i.e., the hydrocarbon heel) from the evaporative canister into the atmosphere. Bleed emissions typically occur, for example, during the heating of the fuel tank during a diurnal cycle. The heating of the fuel tank causes air to flow from the fuel tank, through the canister, out the vent port and into the atmosphere. The air carries the hydrocarbon heel out of the canister and into the atmosphere, thereby resulting in the release of bleed emissions.

In order to reduce bleed emissions some motor vehicles employ an auxiliary canister. The auxiliary canister is placed in series with and further filters the treated air flowing out the vent port of the main evaporative canister. The auxiliary canister typically uses the same sorbent material, i.e., granular or pelletized carbon, as is used in the main evaporative canister to thereby increase the hydrocarbon capacity of the evaporative emission control system. However, in order to achieve sufficient hydrocarbon capacity, auxiliary canisters are generally highly restrictive to the flow of air. Thus, the auxiliary canister must be bypassed in order to be compatible with vehicle refueling vapor recovery systems. Bypassing an auxiliary canister requires the addition of valving and conduits to the evaporative emissions control system, and thus adds cost and complexity to the system. Furthermore, the restrictive air flow characteristics of the auxiliary canister makes purging the volume of sorbent material inefficient, especially in small displacement engines. Moreover, vehicles which incorporate a more efficient evaporative canister and/or an auxiliary canister typically do not reduce bleed emissions to a level required to classify the vehicle as a Super Ultra Low Emissions Vehicle (SULEV) or as a Practically Zero Emissions Vehicle (PZEV).

Therefore, what is needed in the art is a device which reduces the bleed emissions of an evaporative canister and/or the combination of an evaporative canister and an auxiliary canister.

Furthermore, what is needed in the art is a device which reduces the bleed emissions from an evaporative canister and has a low flow restriction, thus rendering the device compatible with vehicle refueling vapor recovery systems.

Yet further, what is needed in the art is a device which reduces bleed emissions from an evaporative canister and has a low flow restriction, thereby increasing purge efficiency.

Even further, what is needed in the art is a device which reduces bleed emissions from an evaporative canister and which has a higher efficiency than an auxiliary canister utilizing carbon pellets or granules.

#### SUMMARY OF THE INVENTION

The present invention provides a hydrocarbon emissions scrubber for use in an evaporative emissions control system of a motor vehicle.

The invention comprises, in one form thereof, a hydrocarbon emissions scrubber including a scrubber element having an elongate body. The body defines a plurality of passageways for the flow of fluid therethrough. The plurality of passageways are one of coated with or constructed of a sorbent material. The sorbent material is adsorptive of hydrocarbons.

An advantage of the present invention is that bleed emissions from an evaporative canister are substantially reduced.

Another advantage of the present invention is the hydrocarbon emissions scrubber is substantially less restrictive to the flow of fluid than a typical auxiliary canister, thereby rendering the device compatible for use in evaporative emissions control systems which incorporate refueling vapor recovery and eliminating the need for complex bypass valving and conduits.

A still further advantage of the present invention is the hydrocarbon emissions scrubber has a higher efficiency than an auxiliary canister.

#### **BRIEF DESCRIPTION OF THE DRAWINGS**

The above-mentioned and other features and advantages of this invention, and the manner of attaining them, will become apparent and be better understood by reference to the following description of one embodiment of the invention in conjunction with the accompanying drawings, wherein:

- FIG. 1 is a plan view of one embodiment of a hydrocarbon bleed emissions scrubber of the present invention.
- FIG. 2 is a longitudinally sectioned view of the hydrocarbon bleed emissions scrubber of Fig. 1;
  - FIG. 3A is a longitudinally sectioned view of the scrubber element of Fig. 2;
  - FIG. 3B is a cross-sectional view of the scrubber element of Fig. 2;
- FIG. 4 is a schematic diagram of one embodiment of an evaporative emissions control system including the hydrocarbon bleed emissions scrubber of Fig. 1.
- FIG. 5 is a fragmentary, longitudinally sectioned view of the hydrocarbon bleed emissions scrubber of Fig. 1;

- FIG. 6 is a longitudinally sectioned view of the hydrocarbon bleed emissions scrubber of Fig. 1;
- FIG. 7 is longitudinally sectioned view of a second embodiment of a hydrocarbon bleed emissions scrubber of the present invention;
- FIG. 8 is a longitudinally sectioned view of a third embodiment of a hydrocarbon bleed emissions scrubber of the present invention;
- FIG. 9 is a plan, partially sectioned view of one embodiment of an evaporative emissions assembly of the present invention;
- FIG. 10 is a plan, partially sectioned view of a second embodiment of an evaporative emissions assembly of the present invention; and
- FIG 11 is a plan, partially sectioned view of a fourth embodiment of a hydrocarbon bleed emissions scrubber of the present invention.

Corresponding reference characters indicate corresponding parts throughout the several views. The exemplification set out herein illustrates one preferred embodiment of the invention, in one form, and such exemplification is not to be construed as limiting the scope of the invention in any manner.

#### **DESCRIPTION OF THE PREFERRED EMBODIMENT**

Referring now to the drawings, and particularly to Figs 1 and 2, there is shown one embodiment of a hydrocarbon emissions scrubber of the present invention.

Hydrocarbon emissions scrubber 10 (hereinafter referred to as HC scrubber 10) includes housing 12, cap 14, scrubber element 16, and flow diffusers 18a and 18b.

Generally, and as will be described more particularly hereinafter, HC scrubber 10 is for

use in an evaporative emissions control system of a motor vehicle. HC scrubber 10 is fluidly connected to an evaporative canister of the evaporative emissions control system, and strips residual fuel vapor and/or hydrocarbons from the air flowing from the evaporative canister before discharging the air into the atmosphere.

Housing 12 is an elongate, substantially cylindrical cup-shaped member having longitudinal central axis A. Housing 12 includes open, flanged end 22, tubular housing end 24 and cylindrical sidewall 26. Flanged end 22 and tubular housing end 24 are interconnected by substantially cylindrical side wall 26. Flange 28 surrounds housing 12 adjacent flanged end 22. Flange 28 is configured to be coupled to cap 14 in an airtight manner, such as, for example, by threadingly engaging or snap-fitting to cap 14. Tubular housing end 24 extends axially from housing 12 at the end thereof which is opposite flanged end 22. Tubular housing end 24 defines a passageway for the flow of air and fuel vapor into and/or out of housing 12. Tubular housing end 24 is slidingly received within a conduit (not shown), and includes barb 30 which resists axial movement of the conduit in a direction away from housing 12. Housing 12 receives scrubber element 16 and flow diffusers 18a, 18b, such that each of scrubber element 16 and flow diffusers 18a, 18b are surrounded by cylindrical side wall 26. Housing 12 is constructed of, for example, an injection molded plastic or other suitable material that is substantially resistant to degradation due to exposure to fuel and fuel vapors.

Cap 14 includes rim end 32 having tubular cap end 34 extending axially therefrom. Rim end 32 includes a substantially saucer-shaped rim 36. Rim 36 is configured to be coupled to flanged end 22 of housing 12 in an air tight manner, such as, for example, threadingly and/or snap-fitting to flange 28 of flanged end 22. Tubular

cap end 34 defines a passageway for the flow of air and fuel vapor through cap 14 into and/or out of housing 12. With cap 14 coupled to flanged end 22 of housing 12, a channel for the flow of fluid through housing 12 is defined by tubular housing end 24, tubular cap end 34 and cylindrical side wall 26. Tubular cap end 34 is configured to be slidingly received within a conduit (not shown), and includes barb 38 which resists axial movement of the conduit in a direction away from housing 12.

Scrubber element 16 is an elongate, substantially cylindrical body and is disposed within housing 12. Referring now to Figs. 3A and 3B, scrubber element 16 has central axis S, a predetermined length L and diameter D. Scrubber element 16 has. in cross-section, a matrix or honeycomb-like structure, and defines a plurality of axial or longitudinal passageways 42 which extend in an axial direction from one end (not referenced) to the other end, i.e., through the entire length L, of scrubber element 16. Disposed between scrubber element 16 and sidewall 26 of housing 12 are resilientlydeformable seals 46a and 46b (Fig. 6). Seals 46a and 46b sealingly engage sidewall 26 to thereby direct fluid and/or air flow through passageways 42 of scrubber element 16 and to prevent fluid and/or air flow through any gap between scrubber element 16 and sidewall 26. Thus, seals 46a and 46b ensure that substantially all of the air and/or fluid flowing into and/or out of housing 12 flows through scrubber element 16. Scrubber element 16 is constructed of a sorbent material 16a, such as, for example, activated carbon. At least the inside surface of each of passageways 42 is formed of or covered with sorbent material 16a. Preferably, scrubber element 16 is extruded from, for example, a slurry-like mixture of sorbent material 16a and a binder.

Flow diffusers 18a and 18b are substantially cylindrical disks that are porous to the flow of air and fuel vapor. Flow diffuser 18a is disposed within housing 12 intermediate scrubber element 16 and tubular housing end 24 such that one side or face (not referenced) of flow diffuser 18a is disposed adjacent to scrubber element 16 and the other face is proximate to tubular housing end 24. Flow diffuser 18b is disposed within housing 12 intermediate scrubber element 16 and cap 14 such that one face of flow diffuser 18b is disposed adjacent scrubber element 16 and the other face is disposed proximate flanged end 22 of housing 12 and proximate to rim 36 of cap 14. Each of flow diffusers 18a and 18b are constructed of, for example, a reticulated foam or other suitable material.

Referring now to Fig. 4, one embodiment of an evaporative emissions control system in accordance with the present invention is shown. Motor vehicle 60 includes internal combustion engine 62 and fuel tank 64. Internal combustion engine 62 has combustion air intake 66. Evaporative emissions control system 70 includes, in addition to HC scrubber 10, vapor conduit 74, evaporative canister 76, vent conduit 78, purge conduit 80, purge valve 82, vent valve 84, and air conduit 86.

Evaporative canister 76 includes purge port 90, vapor inlet port 92 and vent port 94. Purge port 90 is fluidly connected to combustion air intake 66 by purge conduit 80. Purge valve 82 is disposed in fluid communication with purge conduit 80 between purge port 90 and combustion air intake 66, such as, for example, within purge conduit 80, and is operable to selectively control the flow of fuel vapor through purge conduit 80 from purge port 90 to combustion air intake 66. Purge valve 82 is open, for example, when internal combustion engine 62 is running. Vapor inlet port 92 is fluidly connected

to fuel tank 64 by vapor conduit 74. Vent port 94 is fluidly connected to HC scrubber 10 by vent conduit 78. More particularly, vent conduit 78 is fluidly coupled at one end to vent port 94 and at the other end to tubular cap end 34 of HC scrubber 10. Tubular housing end 24 of HC scrubber 10 is fluidly coupled to vent valve 84 by air conduit 86. Vent valve 84 is disposed between HC scrubber 10 and an air intake and/or discharge assembly (not shown), such as, for example, within air conduit 86. Vent valve 84 is operable to selectively control the flow of air through air conduit 86 into and/or out of HC scrubber 10. Vent valve 84 is normally open, and can be selectively closed in conjunction with purge valve 82 to perform various functions, such as, for example, leak detection and vacuum testing of Evaporative emissions control system 70. Each of vent valve 84 and purge valve 82 are electrically connected to, for example, an engine control module (not shown), and open and close in response to signals issued by the engine control module.

In use, HC scrubber 10 is incorporated within evaporative emissions control system 70, and adsorbs hydrocarbons from the bleed emissions flowing out vent port 94 of evaporative canister 76. More particularly, as fuel tank 64 is subjected to diurnal changes in temperature and/or pressure, vapor pressure within fuel tank 64 forces air out of fuel tank 64. The flow of air carries fuel vapor. The air and fuel vapor flow through vapor conduit 74 and into evaporative canister 76. The air and fuel vapor flow through sorbent media (not referenced) contained within evaporative canister 76. The sorbent media strips the hydrocarbons from the air flow. The treated air flows out vent port 94. However, the air flowing out vent port 94 contains bleed emissions. As stated above, bleed emissions are believed to result from the hydrocarbon heel present in the

sorbent material of a purged evaporative canister and typically occur during a diurnal cycle. Thus, the air flowing out vent port 94 contains hydrocarbon heel-based or bleed emissions. The bleed emissions are further removed from the flow of air by HC scrubber 10, thereby reducing the level of hydrocarbons/bleed emissions emitted by evaporative emissions control system 70 relative to a conventional evaporative emissions control system.

The bleed emissions flow into HC scrubber 10 from vent port 94 of evaporative canister 76. More particularly, bleed emissions from evaporative canister 76 flow out vent port 94, through vent conduit 78 and into tubular cap end 34 of HC scrubber 10. The bleed emission flow through flow diffuser 18b which, as shown in Fig. 5, distributes the flow of bleed emissions B uniformly across the cross-sectional area of scrubber element 16 thereby ensuring an even and uniform flow of bleed emissions B<sub>1</sub> relative to the cross-sectional area of scrubber element 16. The uniformly-distributed flow of bleed emissions B<sub>1</sub> substantially equally loads each of passageways 42 with bleed emissions, and exposes the bleed emissions to the cumulative surface area of passageways 42. Each of passageways 42 are lined with or constructed of sorbent material 16a. Thus, the surface area of sorbent material 16a to which the bleed emissions are exposed is maximized, thereby maximizing the capacity of scrubber element 16 to adsorb and store hydrocarbons, through the uniform distribution of bleed emissions by flow diffuser 18b. The cleansed air exits HC scrubber 10 through tubular housing end 24, then through air conduit 86 and vent valve 84, and into the atmosphere.

HC scrubber 10 is purged through normal operation of internal combustion engine 62. At least a portion of the air drawn into combustion air intake 66 flows into

and through HC scrubber 10, and purges HC scrubber 10 of accumulated hydrocarbons. More particularly, during normal operation of engine 62, purge valve 82 is opened thereby fluidly connecting purge port 90 to combustion air intake 66 of internal combustion engine 62. Combustion air intake 66 is at subatmospheric pressure during normal operation of internal combustion engine 62. Vent port 94 is in fluid communication with purge port 90 and, thus, with the subatmospheric pressure present at combustion air intake 66. The subatmospheric pressure present at combustion air intake 66, vent port 94 and purge port 90 draws fresh air in through vent port 94. More particularly, fresh air is drawn into air conduit 86, through vent valve 84 and into tubular housing end 24 of HC scrubber 10. The air is drawn into HC scrubber 10 and through flow diffuser 18a, which distributes the flow of fresh air uniformly across the crosssectional area of scrubber element 16 thereby ensuring an even and uniform flow of fresh air through each of passageways 42 as described above in regard to flow diffuser 18b. The uniform distribution of the fresh air flow relative to the cross-sectional area of scrubber element 16 purges the stored bleed emissions/hydrocarbons from sorbent material 16a which lines each of passageways 42. Thus, the efficiency with which scrubber element 16 and sorbent material 16a is purged of stored hydrocarbons is maximized.

Similarly, evaporative canister 76 of evaporative emissions control system 70 is purged by the flow of fresh air drawn by the vacuum present at combustion air intake 66. The air is drawn through HC scrubber 10 and into evaporative canister 76 through vent port 94. The air flows through the sorbent material contained within evaporative canister 76 thereby purging same of stored hydrocarbons. The air is further drawn by

the vacuum out purge port 90, and carries with it the hydrocarbons purged from each of evaporative canister 76 and HC scrubber 10. The purge air is drawn through purge conduit 90 and into combustion air intake 66 of engine 62. The purged air and/or hydrocarbons are drawn into combustion air intake 66 where they are mixed into and form part of the combustion charge of engine 62. Thus, the purged hydrocarbons are burned and consumed by engine 62.

Referring now to Fig. 8, a second embodiment of an HC scrubber of the present invention is shown. HC scrubber 110, in general, enables the same amount of sorbent material to be incorporated into a package which occupies less space than is occupied by HC scrubber 10. Alternatively, HC scrubber 110 enables a substantial increases in the amount sorbent material within a housing which occupies approximately the same space as occupied by HC scrubber 10. More particularly, HC scrubber 110 includes housing 112, cap 114, scrubber elements 116a and 116b, and flow diffusers 118a, 118b, 118c and 118d.

Cap 114 engages housing 112 in an air and fluid tight manner, such as, for example, by snap-fitting onto housing 112 as described above in regard to housing 12 and cap 14 of HC scrubber 10. Scrubber elements 116a, 116b are each disposed within housing 112. Scrubber elements 116a and 116b are placed in series relative to the flow of bleed emissions, such that bleed emissions will flow first through scrubber element 116a and then through scrubber element 116b. Flow diffusers 118a, 118b are associated with opposite ends of scrubber element 116a, while flow diffusers 118a, 118d are associated with opposite ends of scrubber element 116b. Flow diffusers 118a, 118b, 188c, and 118d serve the same purpose as described above in regard to flow

diffusers 18a and 18b of HC scrubber 10, i.e., the even distribution of the flow of air and bleed emissions relative to the cross-sectional area of scrubber elements 116a and 116b. Each of scrubber elements 116a and 116b are spaced apart by spacing wall 120 of housing 112. Spacing wall 120 guides the flow of bleed emissions and ensures scrubber elements 116a and 116b are in series relative to the flow of bleed emissions. HC scrubber 110 includes cap 114 having tubular housing end 124 and tubular cap end 134, which serve as the inlet and outlet for the flow of bleed emissions into housing 112.

Referring now to Fig. 9, one embodiment of an evaporative emissions assembly of the present invention is shown. Generally, evaporative emissions assembly 200 integrates into a single housing an evaporative emissions canister and an HC scrubber in accordance with the present invention. More particularly, evaporative emissions assembly 200 includes evaporative canister 276 and HC scrubber 210, each of which are disposed within housing 299. Evaporative canister 276 includes purge port 290, vapor inlet port 292 and vent port 294. Evaporative canister 276 contains sorbent material (not shown). Purge port 290 and vapor inlet port 292 are essentially conventional in design and configuration, and are respectively substantially similar in function to purge port 90 and inlet port 92 as discussed above in regard to evaporative canister 76. Vent port 294 forms a passageway for the flow of air into and out of evaporative canister 276. HC scrubber 210 is disposed intermediate and is in fluid communication with each of vent port 294 and evaporative canister 276, such that air flowing into and/or out of evaporative canister 276 through vent port 294 must flow through HC scrubber 210. HC scrubber 210 includes scrubber element 216 and flow diffusers 218a, 218b (only one shown) disposed on opposite ends of scrubber element 216. Scrubber element 216 and flow diffusers 218a, 218b are each substantially similar to scrubber element 16 and flow diffusers 18a, 18b, respectively, as discussed above in regard to HC scrubber 10.

In use, fresh air is drawn into and treated air flows out of evaporative emissions assembly 200 through vent port 294 of evaporative canister 276. HC scrubber 210 is disposed in fluid communication with vent port 294 and evaporative canister 276 such that fresh/purge air flowing into and bleed emissions flowing from evaporative canister 276 must flow through HC scrubber 210. Thus, purge/fresh air entering and bleed emission exiting evaporative emissions assembly 200 must flow through scrubber element 216. As bleed emissions flow through scrubber element 216, hydrocarbons are stripped therefrom by scrubber element 216 in substantially the same manner as discussed above in regard to scrubber element 16 of HC scrubber 10. Further, purge/fresh air is selectively drawn through vent port 294 and into evaporative canister 276, such as, for example, by a vacuum or a combustion air intake fluidly connected to purge port 292. The purge/fresh air flows through scrubber element 216 thereby purging scrubber element 216 of stored hydrocarbons in a manner substantially similar to the purging of scrubber element 16, as described above in regard to HC scrubber 10.

Referring now to Fig. 10, a second embodiment of an evaporative emissions assembly of the present invention is shown. Generally, and similarly to evaporative emissions assembly 200, evaporative emissions assembly 300 integrates into a single assembly an evaporative emissions canister and HC scrubber 310. More particularly, evaporative emissions assembly 300 includes evaporative canister 376 and HC

scrubber 310. Evaporative canister 376 contains sorbent material (not shown), and includes purge port 390, vapor inlet port 392 and vent port 394. Purge port 390, vapor inlet port 392 and vent port 394 are, respectively, substantially similar in function to purge port 90, inlet port 92 and vent port 94 as discussed above in regard to evaporative canister 76. HC scrubber 310 includes housing 312, within which is disposed scrubber element 316 and flow diffusers 318a, 318b (only one shown). Each of housing 312, scrubber element 316 and flow diffusers 318a, 318b are, respectively, substantially similar to scrubber element 16 and flow diffusers 18a, 18b as discussed above in regard to HC scrubber 10. Elongate conduit 380 fluidly and mechanically interconnects vent port 394 of evaporative cannister 376 and tubular cap end 334 of HC scrubber 310.

In use, fresh/purge air is drawn into and treated air flows out of evaporative emissions assembly 300 through tubular housing end 324 of HC scrubber 310. HC scrubber 310 is disposed in fluid communication with vent port 394 of evaporative canister 376 such that fresh/purge air flowing into and bleed emission flowing from vent port 394 of evaporative canister 376 must flow through HC scrubber 310. Thus, purge/fresh air entering and bleed emission exiting evaporative emissions assembly 300 must flow through scrubber element 316.

Bleed emissions flowing from evaporative canister 376 flow through vent port 394 and into tubular cap end 334 of HC scrubber 310. The bleed emissions are channeled through scrubber element 316, which strips hydrocarbons from the bleed emissions in substantially the same manner as discussed above in regard to scrubber element 16 of HC scrubber 10. Further, purge/fresh air is selectively drawn through tubular housing

end 324 into evaporative canister 376, such as, for example, by a vacuum or a combustion air intake fluidly connected to purge port 392. The purge/fresh air flows through scrubber element 316, thereby purging scrubber element 316 of stored hydrocarbons in a manner substantially similar to the purging of scrubber element 16, as described above in regard to HC scrubber 10.

Referring now to Fig. 11, yet another embodiment of an HC scrubber of the present invention is illustrated. HC scrubber 410 includes housing 412 within which is disposed scrubber element 416, each of which are, respectively, substantially similar to housing 12 and scrubber element 16 as discussed above in regard to HC scrubber 10. HC scrubber 410 further includes electrical connector 452 disposed on the outside surface of housing 412. Electrical connector 452 is, for example, integral with or attached to housing 412. Further, HC scrubber 410 includes ceramic heating elements 454. Heating elements 454 are configured as, for example, ceramic disks having electrically conductive film deposited thereon. Electrical wires 456 are connected to electrical connector 452 and to heating elements 454 to thereby supply current to each of heating elements 454. In use, the heating of the air flowing through scrubber element 416 by heating elements 454 increases the efficiency with which the fresh air purges scrubber element 416 of stored hydrocarbons.

In the embodiment shown, housing 12 and scrubber element 16 are substantially cylindrical in shape. However, it is to be understood that the housing and scrubber element may be alternately configured, such as, for example, oval, square, or of any other suitable geometry.

In the embodiment shown, scrubber element 16 is preferably extruded from a mixture of sorbent material with a binder. However, it is to be understood that the scrubber element may be alternately configured, such as, for example, an electrically conductive or semiconductive substrate that is coated or otherwise associated with a sorbent material. Further, electrical current may be conducted through such a substrate to thereby enable the substrate itself to serve as a heating element.

In the embodiment shown, the sorbent material from which the scrubber element is formed is disclosed as being, for example, an activated carbon powder. However, it is to be understood that the sorbent material may be virtually any material that is adsorptive of hydrocarbons.

In the embodiment shown, seals 46 are used to direct the flow of air and/or fluid through scrubber element 16. However, it is to be understood that the hydrocarbon emissions scrubber of the present invention can be alternately configured, such as, for example, as hydrocarbon emissions scrubber 510 having face seals 546a and 546b, as shown in Fig. 7. Face seals 546a and 546b are each disposed intermediate a respective end of scrubber element 516 and a corresponding end of housing 512 to thereby preclude air and/or fluid flow through any gap that may exist between scrubber element 516 and the inside surface of sidewall 526 of housing 512. Face seals 546a and 546b can be constructed of the same material as the housing or can be made from any suitable material that is not porous to the flow of fluid and/or air. Furthermore, in the embodiment shown, there are two seals 46a, 46b. However, it is to be understood that the hydrocarbon emissions scrubber of the present invention can be alternately configured, such as, for example, having no seals, one seal, or any number of seals.

In the embodiment shown, heating elements 454 are configured as, for example, ceramic heating elements. However, it is to be understood that the heating element or elements can be alternately configured, such as, for example, a resistive heating wire wrapped around or embedded in the scrubber element. Further, the scrubber element the may be alternately configured, such as, for example, constructed of an electrically conductive or semiconductive substrate, that is coated or otherwise associated with a sorbent material and through which electrical current may be conducted to thereby enable the substrate itself to serve as a heating element.

In the embodiment shown, evaporative emissions scrubber 16 and vent valve 84 are separate components. However, it is to be understood that the evaporative emissions scrubber may be alternatively configured, such as, for example, to include an integral vent valve, air filter, and/or pump for leak testing within the same housing.

While this invention has been described as having a preferred design, the present invention can be further modified within the spirit and scope of this disclosure. This application is therefore intended to cover any variations, uses, or adaptations of the present invention using the general principles disclosed herein. Further, this application is intended to cover such departures from the present disclosure as come within the known or customary practice in the art to which this invention pertains and which fall within the limits of the appended claims.

#### What is Claimed:

1. A scrubber element, comprising:

an elongate body having a first end and a second end, said body defining a plurality of passageways for the flow of fluid therethrough from said first end to said second end, said plurality of passageways being one of coated with and constructed of a sorbent material, said sorbent material being adsorptive of hydrocarbons.

- 2. The scrubber element of claim 1, wherein said body is constructed at least partially of said sorbent material.
- 3. The scrubber element of claim 1, wherein said body is constructed entirely of said sorbent material.
- 4. The scrubber element of claim 1, wherein said body is extruded from a mixture of said sorbent material and a binder.
- 5. The scrubber element of claim 1, wherein said sorbent material comprises an activated carbon powder.
- 6. The scrubber element of claim 1, further comprising at least one heating element associated with said body.
- 7. The scrubber element of claim 6, wherein said at least one heating element comprises at least a portion of said elongate body, said portion being configured for conducting current therethrough.
- 8. The scrubber element of claim 6, wherein said at least one heating element comprises a resistive heating wire.
  - 9. A hydrocarbon emissions scrubber, comprising:

an elongate housing, said housing defining a channel for a flow of fluid through said housing; and

at least one scrubber element having an elongate body, each of said at least one scrubber element being disposed within said housing and in fluid communication with said channel, each of said at least one scrubber element configured for filtering bleed emissions from the flow of fluid through said channel.

- 10. The hydrocarbon emissions scrubber of claim 9, wherein each said at least one scrubber element is one of constructed at least partially from or coated with a sorbent material, said sorbent material being adsorptive of hydrocarbons.
- 11. The hydrocarbon emissions scrubber of claim 9, wherein said body of each said at least one scrubber element includes a first end and a second end, said body further defining a plurality of elongate passageways for the flow of fluid therethrough from said first end to said second end.
- 12. The hydrocarbon emissions scrubber of claim 11, wherein said passageways are at least one of coated with or constructed at least partially from a sorbent material that is adsorptive of hydrocarbons.
- 13. The hydrocarbon emissions scrubber of claim 9, wherein said at least one scrubber element is extruded from a mixture of an activated carbon powder and a binder.
- 14. The hydrocarbon emissions scrubber of claim 9, further comprising sealing means, said sealing means configured for directing the flow of fluid within said channel through said at least one scrubber element and for precluding a flow of fluid within said channel external to said at least one scrubber element.

- 15. The hydrocarbon emissions scrubber of claim 14, wherein said sealing means comprise at least one resiliently deformable seal, each of said at least one seal being disposed around a periphery of said at least one scrubber element and sealingly engaging each of said periphery of said at least one scrubber element and an inside surface of said housing.
- 16. The hydrocarbon emissions scrubber of claim 14, wherein said sealing means comprise at least one face seal, each of said at least one face seal being disposed intermediate a respective end of said at least one scrubber element and a corresponding end of said housing.
- 17. The hydrocarbon emissions scrubber of claim 9, further comprising at least one heating element disposed within said housing.
- 18. The hydrocarbon emissions scrubber of claim 17, wherein said at least one heating element comprises a ceramic heating element.
- 19. The hydrocarbon emissions scrubber of claim 17, wherein said at least one heating element comprises at least a portion of said body, said portion being configured for conducting electrical current therethrough.
- 20. The hydrocarbon emissions scrubber of claim 17, further comprising an electrical connector, said electrical connector being at least one of integral with and attached to said housing, said electrical connector being electrically connected to said at least one heating element.
- 21. The hydrocarbon emissions scrubber of claim 9, further comprising at least one flow diffuser, each of said at least one flow diffuser being disposed within said housing proximate to a respective end of said body.

- 22. The hydrocarbon emissions scrubber of claim 9, wherein said at least one scrubber element comprises at least two scrubber elements, each of said at least two scrubber elements are disposed within said housing and in fluid communication with said channel.
- 23. The hydrocarbon emissions scrubber of claim 22, wherein each of said at least two scrubber elements are disposed in series relative to a flow of air through said channel such that air flows sequentially through said at least two scrubber elements.
  - 24. An evaporative emissions assembly, comprising:

a housing, said housing defining a purge port, a vent port and a vapor inlet port, sorbent material being disposed within said housing, each of said purge port, said vent port, and said vapor inlet port being in fluid communication with said sorbent media; and a scrubber element disposed within said housing, said scrubber element in fluid communication with said vent port, said scrubber element being disposed intermediate said vent port and said sorbent material such that a flow of air into and out of said vent port flows through said scrubber element.

- 25. The evaporative emissions assembly of claim 24, wherein said scrubber element includes an elongate body having a first and second end, said body defining a plurality of passageways for the flow of fluid therethrough from said first end to said second end, said plurality of passageways being one of coated with and constructed of a sorbent material, said sorbent material being adsorptive of hydrocarbons.
- 26. The evaporative emissions assembly of claim 25, wherein said body is constructed at least partially of said sorbent material.

- 27. The evaporative emissions assembly of claim 25, wherein said body is constructed entirely of said sorbent material.
- 28. The evaporative emissions assembly of claim 25, wherein said body is extruded from a mixture of said sorbent material and a binder.
- 29. The evaporative emissions assembly of claim 25, wherein said sorbent material comprises an activated carbon powder.
- 30. The evaporative emissions assembly of claim 25, further comprising at least one heating element disposed within said housing.
- 31. The evaporative emissions assembly of claim 30, wherein said at least one heating element comprises a ceramic heating element.
- 32. The evaporative emissions assembly of claim 30, wherein said at least one heating element comprises at least a portion of said body, said portion being configured to conduct electrical current.
- 33. The evaporative emissions assembly of claim 30, further comprising an electrical connector being at least one of integral with and attached to said housing, said electrical connector being electrically connected to said at least one heating element.
- 34. The evaporative emissions assembly of claim 25, further comprising at least one flow diffuser, each of said at least one flow diffuser being disposed within said housing proximate to a respective end of said body of said scrubber element.
  - 35. An evaporative emissions assembly, comprising:

an evaporative canister, said evaporative canister defining a purge port, a vent port and a vapor inlet port, sorbent material being disposed within said evaporative canister, each of said purge port, said vent port, and said vapor inlet port being in fluid communication with said sorbent media;

a hydrocarbon emissions scrubber including a housing and a scrubber element, said housing defining a channel for the flow of fluid therethrough, said scrubber element being disposed within said housing and in fluid communication with said channel, said scrubber element configured for filtering bleed emissions from fluid flowing through said channel; and

a conduit fluidly interconnecting said channel of said housing and said vent port of said evaporative canister.

- 36. The evaporative emissions assembly of claim 35, wherein said scrubber element includes an elongate body, said body defining a plurality of passageways for the flow of fluid therethrough, said plurality of passageways being one of coated with and constructed of a sorbent material, said sorbent material being adsorptive of hydrocarbons.
- 37. The evaporative emissions assembly of claim 36, wherein said body is constructed at least partially of said sorbent material.
- 38. The evaporative emissions assembly of claim 36, wherein said body is constructed entirely of said sorbent material.
- 39. The evaporative emissions assembly of claim 36, wherein said body is extruded from a mixture of said sorbent material and a binder.
- 40. The evaporative emissions assembly of claim 36, wherein said sorbent material comprises an activated carbon powder.

- 41. The evaporative emissions assembly of claim 36, further comprising at least one heating element disposed within said housing of said hydrocarbon emissions scrubber.
- 42. The evaporative emissions assembly of claim 41, wherein said at least one heating element comprises at least one ceramic heating element.
- 43. The evaporative emissions assembly of claim 41, wherein said at least one heating element comprises at least a portion of said body, said portion being configured for conducting electrical current.
- 44. The evaporative emissions assembly of claim 41, further comprising an electrical connector being at least one of integral with and attached to said housing, said electrical connector being electrically connected to said at least one heating element.
- 45. The evaporative emissions assembly of claim 36, further comprising at least one flow diffuser, each of said at least one flow diffuser being disposed within said channel and proximate to a respective end of said body.
  - 46. An evaporative emissions control system, comprising: an evaporative canister defining a vent port; and
- a hydrocarbon emissions scrubber defining a channel for a flow of fluid therethrough, said channel being in fluid communication with said vent port, a scrubber element disposed in fluid communication with said channel, said scrubber element configured for filtering bleed emissions from the flow of fluid through said channel.
- 47. A motor vehicle having an evaporative emissions control system, said evaporative emissions control system comprising:


an evaporative canister defining a vent port; and


a hydrocarbon emissions scrubber defining a channel for a flow of fluid therethrough, said channel being in fluid communication with said vent port, a scrubber element disposed in fluid communication with said channel, said scrubber element configured for filtering bleed emissions from the flow of fluid through said channel.


#### **ABSTRACT**


A hydrocarbon emissions scrubber for use in an evaporative emissions control system of a motor vehicle includes a scrubber element having an elongate body. The body defines a plurality of passageways for the flow of fluid therethrough. The plurality of passageways are one of coated with or constructed of a sorbent material. The sorbent material is adsorptive of hydrocarbons.

















FIG. 5









FIG. 8

FIG. 9









a valid OMB control number.

Under the Paperwork Reduction Act of 1995, no persons are required to respond to a collection of information unless it contains

### **DECLARATION FOR UTILITY OR DESIGN PATENT APPLICATION** (37 CFR 1.63)

Declaration Submitted with Initial

Filing

Declaration Submitted after Initial Filing (surcharge (37 CFR 1.16 (e)) required)

| Attorney Docket Number | er      | 89190.145700/DP-302200 |  |  |  |  |  |
|------------------------|---------|------------------------|--|--|--|--|--|
| First Named Inventor   |         | Thomas C. Meiller      |  |  |  |  |  |
| COMPLE                 | TE IF I | KNOWN                  |  |  |  |  |  |
| Application Number     | TBA     | 1                      |  |  |  |  |  |
| Filing Date            | Here    | with                   |  |  |  |  |  |
| Group Art Unit         | Unkn    | nown                   |  |  |  |  |  |
| Examiner Name          | Unkr    | nown                   |  |  |  |  |  |

| As a below named inventor, I hereby declare  |                         |                                |                         |                             |  |  |  |  |  |  |
|--|-------------------------|--------------------------------|-------------------------|-----------------------------|--|--|--|--|--|--|
| My residence, post office address, and citizenship are as stated below next to my name.  |                         |                                |                         |                             |  |  |  |  |  |  |
| I believe I am the original, first and sole inventor (if only one name is listed below) or an original, first and joint inventor (if plural  |                         |                                |                         |                             |  |  |  |  |  |  |
| names are listed below) of the subject matter which is claimed and for which a patent is sought on the invention entitled:   |                         |                                |                         |                             |  |  |  |  |  |  |
| HYDROCARBON BLEED  | EMISSION SCR            | UBBER WITH LOW                 | RESTRICTIO              | N                           |  |  |  |  |  |  |
|  |                         |                                |                         |                             |  |  |  |  |  |  |
| L  |                         |                                |                         |                             |  |  |  |  |  |  |
| the specification of which   | (Trtle                  | of the Invention)              |                         |                             |  |  |  |  |  |  |
| is attached hereto   | ,                       | ,                              |                         |                             |  |  |  |  |  |  |
| OR   |                         |                                |                         |                             |  |  |  |  |  |  |
| was filed on (MM/DD/YYYY)  |                         | as Unit                        | ted States Application  | Number or PCT International |  |  |  |  |  |  |
| Application Number TBA   | and wa                  | s amended on (MM/DD/YYY        | Υ)                      | (if applicable)             |  |  |  |  |  |  |
| I hereby state that I have reviewed and u  | nderstand the contents  | of the above identified speci  | fication, including the | claims, as                  |  |  |  |  |  |  |
| amended by any amendment specifically  | referred to above.      |                                |                         |                             |  |  |  |  |  |  |
| I acknowledge the duty to disclose inform  | ation which is material | to natentability as defined in | 37 CFR 1 56             |                             |  |  |  |  |  |  |
| Tablino modgo kilo daly to discisso line.  |                         | to paternability as dominos in | 0. 0. 1. 1.00.          |                             |  |  |  |  |  |  |
| I hereby claim foreign priority benefits under 35 U.S.C. 119(a)-(d) or 365(b) of any foreign application(s) for patent or inventor's certificate, or 365(a) of any PCT international application which designated at least one country other than the United States of America, listed below and have also identified below, by checking the box, any foreign application for patent or inventor's certificate, or of any PCT international application having a filing date before that of the application on which priority is claimed |                         |                                |                         |                             |  |  |  |  |  |  |
| Prior Foreign Application  |                         | Foreign Filing Date            | Priority                | Certified Copy Attached?    |  |  |  |  |  |  |
| Number(s)  | Country                 | (MM/DD/YYYY)                   | Not Claimed             | YES NO                      |  |  |  |  |  |  |
| NT.  |                         |                                |                         |                             |  |  |  |  |  |  |
| None   |                         |                                |                         |                             |  |  |  |  |  |  |
|  |                         | <b>E</b>                       |                         |                             |  |  |  |  |  |  |
|  |                         |                                |                         |                             |  |  |  |  |  |  |
|  |                         |                                |                         |                             |  |  |  |  |  |  |
| Additional foreign application numbers   | are listed on a supple  | mental priority data sheet PT  | O/SB/02B attached he    | ereto.                      |  |  |  |  |  |  |
| I hereby claim the benefit under 35 U.S.0  | C. 119(e) of any United | States provisional applicatio  | n(s) listed below.      |                             |  |  |  |  |  |  |
| Application Number(s)  | Filing Date (           | MM/DD/YYYY)                    |                         |                             |  |  |  |  |  |  |
|  |                         | ·                              |                         |                             |  |  |  |  |  |  |
| 60/192,917   | March 29, 200           | ۱                              | اسسسا                   | nal provisional application |  |  |  |  |  |  |
| 00/172,71/   | 141011 29, 200          | ٧                              |                         | rs are listed on a          |  |  |  |  |  |  |
|  |                         |                                | • •                     | mental priority data sheet  |  |  |  |  |  |  |
|  |                         |                                | PIOS                    | B/02B attached hereto.      |  |  |  |  |  |  |
|  |                         |                                |                         |                             |  |  |  |  |  |  |

[Page 1 of 2]

Burden Hour Statement This form is estimated to take 0.4 hours to complete. Time will vary depending upon the needs of the individual case. Any comments on the amount of time you are required to complete this form should be sent to the Chief Information Officer, Patent and Trademark Office, Washington, DC 20231. DO NOT SEND FEES OR COMPLETED FORMS TO THIS ADDRESS SEND TO:

PTO/SB/01 (12-97)

this box 

Approved for use through 9/30/00. OMB 0651-0032

Patent and Trademark Office; U.S. DEPARTMENT OF COMMERCE

Under the Paperwork Reduction Act of 1995, no persons are required to respond to a collection of information unless it contains a valid OMB control number.

# **DECLARATION**—Utility or Design Patent Application

|                         |                          |  |                              |  |                                 |                        |                       | _                   |             |            |                         |                                     |                                |
|-------------------------|--------------------------|--|------------------------------|--|---------------------------------|------------------------|-----------------------|---------------------|-------------|------------|-------------------------|-------------------------------------|--------------------------------|
| application in the      | below and,<br>e manner p | t under 35 U.S.C. 1<br>d, insofar as the su<br>provided by the first<br>le available betweer | subject matt<br>st paragraph | tter of each of the<br>oh of 35 U.S.C. 112 | ne claims of t<br>12. Lacknowle | this app<br>edge the   | plication<br>aduly to | i is not<br>disclos | t disclosed | in the pr  | rior Unite              | ed States or Po                     | CT International               |
|                         | S. Pare                  | ent Application  | or PCT                       | Parent                                     |                                 | 1                      | ent Fili              | -                   |             |            |                         | nt Patent No                        |                                |
| None                    | Numbe.                   | <u>i</u>   |                              |  | <del></del>                     | (IVI                   | IM/DD/                | <u>/Y Y 1</u>       | <u>Y)</u>   | -          |                         | (if applicabl                       | <u>e)</u>                      |
| None                    |                          |  |                              |  |                                 |                        |                       |                     |             |            |                         |                                     |                                |
|                         |                          | T international app  |                              |  |                                 |                        |                       |                     |             |            |                         |                                     |                                |
|                         | ntor, I hereb            | by appoint the follo   | owing regist                 | stered practitioner(                       | r(s) to prosecu                 |                        |                       |                     |             |            |                         | he Patent                           |                                |
| anu mauement            | fice co                  | :cted merewini.  |                              | Customer Numbe<br>OR                       | it T                            |                        |                       |                     | _ -         |            | +                       | Place Custo<br>Number Bar           |                                |
|                         |                          |  | <b>~</b>                     | Registered practit                         |                                 | ne/regist              | tration n             | iumber              | listed belo | w          |                         | Label hei                           | ere                            |
|                         | Nam                      | 1e   | !                            | Registr<br>Num                             |                                 |                        | l                     |                     | Nam         | ne         | _                       |                                     | gistration<br>lumber           |
| Thomas R. F             | itzGera                  | ıld  |                              | 26,730                                     | -                               | $\overline{}$          | Rona                  | ald S               | . Kareke    | en         |                         | 20,573                              |                                |
| Lee J. Flecke           |                          |  | !                            | 36,136                                     |                                 | ļ                      | 1                     |                     | S. Road     |            |                         | 45,044                              |                                |
| Ronald J. Kis           |                          |  | 1                            | 38,205                                     |                                 | ļ                      | Stepl                 | hen J               | J. Sand     |            |                         | 34,716                              | 5                              |
| John VanOpl             |                          | - the restol nam   |                              | 38,646                                     |                                 |                        | <u> </u>              |                     |             |            |                         |                                     |                                |
|                         |                          | oractitioner(s) name   |                              | ı  | ad Practitions                  | er Intorn              | nation sr             | neet P              | TO/SB/020   | 2 attached | hereto.                 |                                     |                                |
| Direct all corres       | pondence                 |  | Custome<br>Bar Code          | er Number or<br>le Label                   |                                 |                        |                       |                     | OR          | Cc         | rrespon                 | ndence addre                        | ss below                       |
| Name                    | John V                   | VanOphem, Es   | sq.                          |  |                                 |                        |                       |                     |             |            |                         |                                     |                                |
| Address                 | Delph                    | i Technologies   | s, Inc.                      |  |                                 |                        |                       |                     |             |            |                         |                                     |                                |
| Address                 | P.O. B                   | Box 5052, Mai  | il Code 4                    | 480414420                                  |                                 | <del></del>            | $\overline{}$         |                     |             | т          | т—                      |                                     |                                |
| City                    | Troy                     |  |                              |  | <del></del>                     | St                     | ate                   | MI                  |             | ZIP        | 4800                    | 7                                   | ·                              |
| Country                 | USA                      |  |                              | Telephone                                  |                                 | 267-5                  |                       |                     |             | Fax        | <u> </u>                | ) 267-5559                          | '                              |
| Turtier that these      | statements               | atements made her<br>ts were made with ti<br>willful false stateme                           | the knowled                  | edge that willful fals                     | ilse statement                  | its and th             | he like si            | so made             | e are nunis | chahla hv  | and belie<br>fine or in | of are believed<br>inprisonment, or | to be true; and both, under 18 |
| Name of Sole            | or Firs                  | t Inventor:  |                              |  |                                 |                        | \ petitio             | n has               | been file   | d for this | unsign                  | ned inventor                        |                                |
| Giv                     | ven Nam                  | e (first and middl   | le [if any]                  | )  |                                 | Family Name or Surname |                       |                     |             |            |                         |                                     |                                |
| Thomas C.               |                          | <del>-                                    </del>   |                              |  |                                 | Me                     | iller                 |                     |             |            |                         |                                     |                                |
| Inventor's<br>Signature |                          | How  | mi C                         | Meil                                       | ly_                             |                        |                       |                     |             |            |                         | Date                                | 10-26-0                        |
| Residence: Cit          | .ty                      | Pittsford  |                              | State                                      | NY                              | Cr                     | ountry                | U                   | JSA         |            |                         | Citizenship                         | USA                            |
| Post Office Add         | dress                    | 20 Langston  | ı Point                      |  |                                 |                        |                       |                     |             |            |                         |                                     |                                |
| Post Office Add         | dress                    |  | •                            |  | <del></del>                     |                        |                       |                     |             |            |                         |                                     |                                |
| City                    |                          | Pittsford  | State                        | NY   | ZIP                             | 14:                    | 534                   |                     |             | Coun       | ntry                    | USA                                 |                                |
| Additional in           | wontore :                | ara haina namar  | d on the                     | 1 sur                                      | onlemental                      | ^dditio                | nal law               | enter(              | a) chaot/   | -\ DTO/5   | י אפטיםי                | attached here                       |                                |

Patent and Trademark Office, U.S. DEPARTMENT OF COMMERCE Under the Paperwork Reduction Act of 1995, no persons are required to respond to a collection of information unless it contains a

## **DECLARATION**

valid OMB control number.

### ADDITIONAL INVENTOR(S) Supplemental Sheet Page 1 of 1

|  |                                       | -          |          |                        |                        |                  |           |           |         |          |  |
|--|---------------------------------------|------------|----------|------------------------|------------------------|------------------|-----------|-----------|---------|----------|--|
| Name of Addition   | nal Joint Inventor, if any            | <i>r</i> : |          |                        | A petition             | on has been file | ed for th | nis unsig | ned in  | ventor   |  |
| Given Na   | ame (first and middle [if any])       | )          |          | Family Name or Surname |                        |                  |           |           |         |          |  |
| Charles H.   |                                       |            |          | Covert                 |                        |                  |           |           |         |          |  |
| Inventor's<br>Signature  | Charles H.                            | 6          | i<br>ver | 1                      |                        |                  |           | Date      | ,       | 10/26/00 |  |
| Residence. City  | Manchester                            | State      | NY       |                        | Country                | USA              |           | Citizens  | hip     | USA      |  |
| Post Office Address  | 30 South Avenue                       |            |          |                        |                        |                  |           |           |         |          |  |
| Post Office Address  |                                       |            |          |                        |                        |                  |           |           |         |          |  |
| City   | Manchester                            | State      | NY       |                        | ZIP                    | 14504            | Country   | , USA     |         |          |  |
| Name of Additional Joint Inventor, if any:  A petition has been filed for this unsigned inventor |                                       |            |          |                        |                        |                  | /entor    |           |         |          |  |
| Given Name (first and middle [if any]) Family Name or Surname                                    |                                       |            |          |                        |                        |                  |           |           |         |          |  |
| Susan S.   |                                       |            |          |                        | LaBine                 |                  |           |           |         |          |  |
| Inventor's<br>Signature  | Iran Lot                              | Zal        | عه       |                        |                        |                  |           |           | ate     | 2406600  |  |
| Residence <sup>-</sup> City  | Avon                                  | State      | NY       |                        | Country                | USA              |           | Citize    | nship   | USA      |  |
| Post Office Address  | 290 Genesee Street                    |            |          |                        |                        |                  |           |           |         |          |  |
| Post Office Address  |                                       |            |          |                        |                        |                  |           |           |         |          |  |
| City   | Avon                                  | State      | NY       |                        | ZIP                    | 14414            | Coun      | try [     | JSA     |          |  |
| Name of Addition   | al Joint Inventor, if any:            | :          |          |                        | A petitio              | on has been file | d for thi | is unsigr | ned inv | entor    |  |
| Given Na   | me (first and middle [if any])        |            |          |                        | Family Name or Surname |                  |           |           |         |          |  |
|  | , , , , , , , , , , , , , , , , , , , |            |          |                        |                        |                  |           | <br>      |         |          |  |
| Inventor's<br>Signature  |                                       |            |          |                        |                        |                  |           | Da        | ite     |          |  |
| Residence: City  |                                       | State      |          |                        | Country                |                  |           | Cıtizer   | ıship   |          |  |
| Post Office Address  |                                       |            |          |                        |                        |                  |           |           |         |          |  |
| Post Office Address  |                                       |            |          |                        |                        |                  |           |           |         |          |  |
| City   |                                       | State      |          |                        | ZIP                    |                  | C         | ountry    |         |          |  |

Burden Hour Statement: This form is estimated to take 0.4 hours to complete. Time will vary depending upon the needs of the individual case. Any comments on the amount of time you are required to complete this form should be sent to the Chief Information Officer, Patent and Trademark Office, Washington, DC 20231. DO NOT SEND FEES OR COMPLETED FORMS TO THIS ADDRESS SEND TO: Assistant Commissioner for Patents, Washington, DC 20231.